


*Necessary preliminary tasks:*

- Remove head restraint at rear left.
- Remove panel for roof pillar on rear left.



Unlock plug connections (1) and disconnect.

Release screws (2).

Remove antenna amplifier (3) in direction of arrow.